

W. 193

Begin

Zelikman, A.

S/149/61/bco/co2/017/017
AC06/AC01

AUTHOR: Zelikman, A.

TITLE: Inter-VUZ Conference on Methods of Separating Rare Metals of Similar Properties

PERIODICAL: Izvestiya vysshikh uchebnykh zavedeniy, Tsvetnaya metallurgiya, 1961, No. 2, pp. 166 - 167

TEXT: A Conference on methods of separating rare metals with similar properties was convened from November 15 to 18, 1960 at the Institute of Non-Ferrous Metals imeni M.I. Kalinin. Over 250 delegates from 10 VUZes, 13 institutes of the Academy of Sciences of the USSR and the Union Republics, 20 scientific research institutes, and a number of plants attended the Conference. The Conference heard 56 reports: 14 on separating zirconium and hafnium; tantalum and niobium; 13 reports on their separation from titanium; and 15 on their separation from rare-earth elements. The other reports dealt with methods of separating tungsten and molybdenum; indium and tin; gallium and aluminum; selenium and tellurium; the separation of alkali rare metals, and deep cleaning of germanium. The following papers were delivered on ion-exchange methods: M.M. Sonyavin on

Card 1/4

S/149/51/000/002/017/017
A006/A001

Inter-VUZ Conference on Methods of Separating Rare Metals of Similar Properties

"Chromatographic Preparation of Pure Rare Metal Materials"; B.N. Laskorin on "Ion-Exchange and Chemo-Sorption Processes in the Hydrometallurgy of Non-Ferrous Metals"; L.I. Martynenko, on the mechanism of separating macro-amounts of rare-earth elements; N.P. Kalonina and N.P. Magda, on results of semi-industrial checking of a method using sorption from hydrofluoric acid solutions; Ye.A. Subbotina, D.M. Chiznikov and others on the possibility of sorption from hydrochloric acid solutions; B.N. Laskorin, G.Ye. Kaplan and A.M. Arzhatkin on continuous chromatographical method of separating zirconium and hafnium; D.M. Ryabobikov and his collaborators on separating selenium and tellurium by the ion-exchange method using sorption on cationites and anionites. Extraction methods were treated in the following papers: G.V. Karpusov on extraction methods of separating rare-earth elements; V.M. Mikhaylov and V.G. Torgov on the use of complexing agents during extraction of rare-earth elements; Z.A. Snaka and Ye.Ye. Kriss on the use of di-butyl phosphate as complexing agent; N.I. Gal'porin and V.L. Pabalk on continuous extraction separation of elements of the cerium group; A.I. Vaysenberg, T.P. Zhitkova and L.A. Kelchina on conditions of extracting tantalum and niobium from hydrofluoric acid solutions with cyclohexane and tri-n-yl phosphate; G.Ye. Kaplan, B.N. Laskorin and others on the use of tri-n-yl amine for extracting tantalum and ni-

Card 3/4

8/14/61/000/002/017/017
A006/A001

Inter-VUZ conference on Methods of Separation of Rare Metals or Similar Properties

biography V.K. Kulifeyev and V.Z. Kapanyashchik on extraction of tantalum, niobium and titanium from hydrochloric acid solutions by commercial alcohol; G.Ye. Kaplan, O.A. Yegodina and others on results of investigating extraction separation of zirconium and hafnium using amines, phosphorous organic compounds and other extracting agents; D.L. Motov and T.G. Loskutov on extraction of zirconium and hafnium from sulfuric acid solutions with cyclohexane; I.V. Vinarov and others on preparing pure hafnium dioxide by rhodanide extraction. The methods of fractional precipitation and crystallization were treated in the following papers: D.M. Chiznikov, E.Ye. Tratsevitskaya and others on results of investigating separation of titanium, niobium and tantalum on the basis of the solubility of their complex chlorine salts; phosphoric acid compounds (A.P. Entin, A.K. Sharova) and sulfuric acid complex compounds (Ya.G. Gorshachenko); B.D. Stepin and V.Ye. Flyusheva on separating rubidium and potassium, based on the different stability of their bromochlorides. The following reports treated the methods of distillation and rectification: L.A. Hise, son, on methods of separating and refining zirconium and hafnium, tantalum and niobium on the basis of different volatility of their halides; A.N. Zelikman, O.Ye. Kreyn and others, on results of studying the se-

Card 3/4

ZELIEMAN, A

MEYERSON, Grigoriy Abramovich; ZELIEMAN, Abram Naumovich; BOL'SHAKOV, K.A.,
prof.dokt., retsenzent; ABRIKOSOV, G.M., dokt.kand.nauk, retsenzent;
MASLANKIN, I.S., prof.dokt., retsenzent; GREYVER, H.S., prof.,
dokt., retsenzenc; VYETSUKA, V.N., red.; KAMAYEVA, O.M., red.
izd-va; ATTOPOVICH, M.K., tekhn.red.

[Metallurgy of rare metals] Metalluriiia redkikh metallov. Moskva,
Gos. nauchno-tekhn. izd-vo lit-ry po chernoi i tsvetnoi metallurgii,
1995. 608 p. (MIRA 11:4)

1. Kafedra metallurgii tsvetnykh i redkikh metallov Leningradskogo
gornogo instituta (for Maslyanitskiy, Greyver)
(Metallurgy)

ZELIKMAN, A. I.

A. I. Zelikman: "Experience of the experimental examination of the effect of stabilizing selection on the fertility of *Cyclops cerrutatus*." (p. 239)

SO: Journal of General Biology Vol. 7, No. 4, 1944

ZELIKMAN, A. L. DOCENT

18 2/49T84

USSR/Medicine - Biology
Medicine - Evolution

Jan 48

"Moscow Conference on Problems of Darwinism," Prof
V. I. Polyanskiy, Docent A. L. Zelikman, 3 pp

"Priroda" No 6

Conference which convened in Moscow 3-8 Feb 48 was
of interest not only to biologists, but also to
large number of Soviet intelligentsia. This was
first such conference in Soviet Union. Lists
people who contributed to proceedings, and some of
the problems discussed.

2/49T84

ZELIKMAN, A. L.

PA 68T83

USSR/Medicine - Zoology
Medicine - Fecundity

May 1948

"Fertility of Cyclops in Cultures of Various
Densities," A. L. Zelikman, A. K. Geynrikh, Inst
Zool, Moscow State U imeni M. V. Lomonosov, 3 pp

"Dok Ak Nauk SSSR" Vol LX, No 5

Studies conducted to determine effect of numbers on
quality of factors in process of evolution of a
type. Devotes special attention to relation of
fertility of cyclops to densities of their popula-
tions. Submitted by Academician I. I. Shmal'gauzen
15 Mar 1948.

FIG

68T83

USSR/General Biology. General Hydrobiology.

B-6

Abs Jour : Russ. Jour-Biol., No 16, 1958, 71676

Author : Zelikman, A. L.

Inst : Kostroma Pedagogical Institute.

Title : Feeding Base for Young Fish in the Reservoirs
of the Volga-Kostroma Bottom Lands.

Orig Pub : Uch. zap. Kostromsk. ped. in-ta, 1957, vyp. 2,
129-191

Abstract : The physical and geographical characteristics
of the reservoirs of the Volga-Kostroma bot-
tom lands are given. The zooplankton of the
lakes of this bottom land are studied, such
as the Sloinskoye and the Velikoye, as well
as the five small rivers which later connect
with the lakes or with the Kostroma river.

Card : 1/2

ZELIKMAN, A.I.

Ch.Darwin's views of the role of "saltations" in the historical
development of organisms [with summary in English]. Biul.MOIP.
Otd.biol. 62 no.1:89-95 Ja-F '57. (MIRA 10:6)
(EVOLUTION)

ZELIKMAN, A.L.; GEYNRIKH, A.K.

Effect of the density of the population on the development
of its components and the mortality rate in Cyclops (Copepoda,
Cyclopidae). Biul.MOIP.Otd.biol. 64 no.4:125-139 J1-Ag
'59. (MIRA 13:4)
(Animal populations) (Copepoda)

ZELIKMAN, A.L.

Quantitative characteristics of zooplankton in waters of the
Volga-Kostroma flood plain. Trudy Gidrobiol. ob-va 10:86-
101 '60. (MIRA 13:9)

(Kostroma Valley--Zooplankton)
(Volga Valley--Zooplankton)

ZELIKMAN, A.I.; PROZOROV, A.A.

Reviews and bibliography. Genetika no.2:170-178 Ag '65.
(MIRA 18:10)

2

MA

Magnesium and Its Alloys. (Hall.) See p. 101.
"On the Equilibrium Diagram of the System Nickel-Niobium." S. A. Pogodin and A. N. Zelikman (*Compt. Rend. (Doklady) Acad. Sci. U.R.S.S.*, 1941, [N.S.], 21, (9), 895-897).—[In German.] The nickel-niobium system was examined in the range 0-63% niobium by the methods of thermal analysis, annealing and quenching, hardness, and electrical conductivity. Alloys were prepared mostly from nickel from 0.7% niobium 0.7% copper 0.1% cobalt and containing 1% titanium 0.1% b. The diagram shows a eutectic at 1250° C. and 24.5% niobium between Ni_3Nb and the primary solid solution of niobium in nickel, and a eutectic at 1175° C. and 51.6% niobium between Ni_3Nb and a further compound ($NiNb_2$), which undergoes a peritectic reaction at 1250° C. Hardness-composition curves showed that at 900° C. (15 hrs. anneal) the Ni_3Nb phase has a homogeneous range from 32.5 to 36% niobium, while the solubility of niobium in nickel is 16.7%. The Ni_3Nb phase melts at a maximum on the liquidus of 1403° C. Solubility values for niobium in nickel, as deduced from annealing experiments at 900° C. (15 hrs.), 1100° C. (15 hrs.), and 1200° C. (15 hrs.), are, respectively, 10%, 15, and 18% niobium. At 1250° C. the solubility was deduced from a cooling curve to be 20% niobium. These solubility values follow the usual logarithmic relation. (G. V. R.)

1943

117 AND 118 SERIES PROPERTIES AND PROPERTIES INDEX

2

Phase of variable composition in the system nickel-
cobalt. A. A. Papisov and A. N. Zolotarev. Ann.
rel. anal. phys. chem., Int. Chem. U.S.S.R. 16,
No. 1, 153-55 (1943) - See C.A. 37, 522. H. M. L.

ASS-ELA METALLURGICAL LITERATURE CLASSIFICATION

1950-1959

1960-1969

1970-1979

1980-1989

1990-1999

2000-2009

2010-2019

2020-2029

2030-2039

2040-2049

2050-2059

2060-2069

2070-2079

2080-2089

2090-2099

2100-2109

2110-2119

2120-2129

2130-2139

2140-2149

2150-2159

2160-2169

2170-2179

2180-2189

2190-2199

2200-2209

2210-2219

2220-2229

2230-2239

2240-2249

2250-2259

2260-2269

2270-2279

2280-2289

2290-2299

2300-2309

2310-2319

2320-2329

2330-2339

2340-2349

2350-2359

2360-2369

2370-2379

2380-2389

2390-2399

2400-2409

2410-2419

2420-2429

2430-2439

2440-2449

2450-2459

2460-2469

2470-2479

2480-2489

2490-2499

2500-2509

2510-2519

2520-2529

2530-2539

2540-2549

2550-2559

2560-2569

2570-2579

2580-2589

2590-2599

2600-2609

2610-2619

2620-2629

2630-2639

2640-2649

2650-2659

2660-2669

2670-2679

2680-2689

2690-2699

2700-2709

2710-2719

2720-2729

2730-2739

2740-2749

2750-2759

2760-2769

2770-2779

2780-2789

2790-2799

2800-2809

2810-2819

2820-2829

2830-2839

2840-2849

2850-2859

2860-2869

2870-2879

2880-2889

2890-2899

2900-2909

2910-2919

2920-2929

2930-2939

2940-2949

2950-2959

2960-2969

2970-2979

2980-2989

2990-2999

3000-3009

3010-3019

3020-3029

3030-3039

3040-3049

3050-3059

3060-3069

3070-3079

3080-3089

3090-3099

3100-3109

3110-3119

3120-3129

3130-3139

3140-3149

3150-3159

3160-3169

3170-3179

3180-3189

3190-3199

3200-3209

3210-3219

3220-3229

3230-3239

3240-3249

3250-3259

3260-3269

3270-3279

3280-3289

3290-3299

3300-3309

3310-3319

3320-3329

3330-3339

3340-3349

3350-3359

3360-3369

3370-3379

3380-3389

3390-3399

3400-3409

3410-3419

3420-3429

3430-3439

3440-3449

3450-3459

3460-3469

3470-3479

3480-3489

3490-3499

3500-3509

3510-3519

3520-3529

3530-3539

3540-3549

3550-3559

3560-3569

3570-3579

3580-3589

3590-3599

3600-3609

3610-3619

3620-3629

3630-3639

3640-3649

3650-3659

3660-3669

3670-3679

3680-3689

3690-3699

3700-3709

3710-3719

3720-3729

3730-3739

3740-3749

3750-3759

3760-3769

3770-3779

3780-3789

3790-3799

3800-3809

3810-3819

3820-3829

3830-3839

3840-3849

3850-3859

3860-3869

3870-3879

3880-3889

3890-3899

3900-3909

3910-3919

3920-3929

3930-3939

3940-3949

3950-3959

3960-3969

3970-3979

3980-3989

3990-3999

4000-4009

4010-4019

4020-4029

4030-4039

4040-4049

4050-4059

4060-4069

4070-4079

4080-4089

4090-4099

4100-4109

4110-4119

4120-4129

4130-4139

4140-4149

4150-4159

4160-4169

4170-4179

4180-4189

4190-4199

4200-4209

4210-4219

4220-4229

4230-4239

4240-4249

4250-4259

4260-4269

4270-4279

4280-4289

4290-4299

4300-4309

4310-4319

4320-4329

4330-4339

4340-4349

4350-4359

4360-4369

4370-4379

4380-4389

4390-4399

4400-4409

4410-4419

4420-4429

4430-4439

4440-4449

4450-4459

4460-4469

4470-4479

4480-4489

4490-4499

4500-4509

4510-4519

4520-4529

4530-4539

4540-4549

4550-4559

4560-4569

4570-4579

4580-4589

4590-4599

4600-4609

4610-4619

4620-4629

4630-4639

4640-4649

4650-4659

4660-4669

4670-4679

4680-4689

4690-4699

4700-4709

4710-4719

4720-4729

4730-4739

4740-4749

4750-4759

4760-4769

4770-4779

4780-4789

4790-4799

4800-4809

4810-4819

4820-4829

4830-4839

4840-4849

4850-4859

4860-4869

4870-4879

4880-4889

4890-4899

4900-4909

4910-4919

4920-4929

4930-4939

4940-4949

4950-4959

4960-4969

4970-4979

4980-4989

4990-4999

5000-5009

5010-5019

5020-5029

5030-5039

5040-5049

5050-5059

5060-5069

5070-5079

5080-5089

5090-5099

5100-5109

5110-5119

5120-5129

5130-5139

5140-5149

5150-5159

5160-5169

5170-5179

5180-5189

5190-5199

5200-5209

5210-5219

5220-5229

5230-5239

5240-5249

5250-5259

5260-5269

5270-5279

5280-5289

5290-5299

5300-5309

5310-5319

5320-5329

5330-5339

5340-5349

5350-5359

5360-5369

5370-5379

5380-5389

5390-5399

5400-5409

5410-5419

5420-5429

5430-5439

5440-5449

5450-5459

5460-5469

5470-5479

5480-5489

5490-5499

5500-5509

5510-5519

5520-5529

5530-5539

5540-5549

5550-5559

5560-5569

5570-5579

5580-5589

5590-5599

5600-5609

5610-5619

5620-5629

5630-5639

5640-5649

5650-5659

5660-5669

5670-5679

5680-5689

5690-5699

5700-5709

5710-5719

5720-5729

5730-5739

5740-5749

5750-5759

5760-5769

5770-5779

5780-5789

5790-5799

5800-5809

5810-5819

5820-5829

5830-5839

5840-5849

5850-5859

5860-5869

5870-5879

5880-5889

5890-5899

5900-5909

5910-5919

5920-5929

5930-5939

5940-5949

5950-5959

5960-5969

5970-5979

5980-5989

5990-5999

6000-6009

6010-6019

6020-6029

6030-6039

6040-6049

6050-6059

6060-6069

6070-6079

6080-6089

6090-6099

6100-6109

6110-6119

6120-6129

6130-6139

6140-6149

6150-6159

6160-6169

6170-6179

6180-6189

6190-6199

6200-6209

6210-6219

6220-6229

6230-6239

6240-6249

6250-6259

6260-6269

6270-6279

6280-6289

6290-6299

6300-6309

6310-6319

6320-6329

6330-6339

6340-6349

6350-6359

6360-6369

6370-6379

6380-6389

6390-6399

6400-6409

6410-6419

6420-6429

6430-6439

6440-6449

6450-6459

6460-6469

6470-6479

6480-6489

6490-6499

6500-6509

6510-6519

6520-6529

6530-6539

6540-6549

6550-6559

6560-6569

6570-6579

6580-6589

6590-6599

6600-6609

6610-6619

6620-6629

6630-6639

6640-6649

6650-6659

6660-6669

6670-6679

6680-6689

6690-6699

6700-6709

6710-6719

6720-6729

6730-6739

6740-6749

6750-6759

6760-6769

6770-6779

6780-6789

6790-6799

6800-6809

6810-6819

6820-6829

6830-6839

6840-6849

6850-6859

6860-6869

6870-6879

6880-6889

6890-6899

6900-6909

6910-6919

6920-6929

6930-6939

6940-6949

6950-6959

6960-6969

6970-6979

6980-6989

6990-6999

7000-7009

7010-7019

7020-7029

7030-7039

7040-7049

7050-7059

7060-7069

7070-7079

7080-7089

7090-7099

7100-7109

7110-7119

7120-7129

7130-7139

7140-7149

7150-7159

7160-7169

7170-7179

7180-7189

7190-7199

7200-7209

7210-7219

7220-7229

7230-7239

7240-7249

7250-7259

7260-7269

7270-7279

7280-7289

7290-7299

7300-7309

7310-7319

7320-7329

7330-7339

7340-7349

7350-7359

7360-7369

7370-7379

7380-7389

7390-7399

7400-7409

7410-7419

7420-7429

7430-7439

7440-7449

7450-7459

7460-7469

7470-7479

7480-7489

7490-7499

7500-7509

7510-7519

7520-7529

7530-7539

7540-7549

7550-7559

7560-7569

7570-7579

7580-7589

7590-7599

7600-7609

7610-7619

7620-7629

7630-7639

7640-7649

7650-7659

7660-7669

7670-7679

7680-7689

7690-7699

7700-7709

7710-7719

7720-7729

7730-7739

7740-7749

7750-7759

7760-7769

7770-7779

7780-7789

7790-7799

7800-7809

7810-7819

7820-7829

7830-7839

7840-7849

7850-7859

7860-7869

7870-7879

7880-7889

7890-7899

7900-7909

7910-7919

7920-7929

7930-7939

7940-7949

7950-7959

7960-7969

7970-7979

7980-7989

7990-7999

8000-8009

8010-8019

8020-8029

8030-8039

8040-8049

8050-8059

8060-8069

8070-8079

8080-8089

8090-8099

8100-8109

8110-8119

8120-8129

8130-8139

8140-8149

8150-8159

8160-8169

8170-8179

8180-8189

8190-8199

8200-8209

8210-8219

8220-8229

8230-8239

8240-8249

8250-8259

8260-8269

8270-8279

8280-8289

8290-8299

8300-8309

8310-8319

8320-8329

8330-8339

8340-8349

8350-8359

8360-8369

8370-8379

8380-8389

8390-8399

8400-8409

8410-8419

8420-8429

8430-8439

8440-8449

8450-8459

8460-8469

8470-8479

8480-8489

8490-8499

8500-8509

8510-8519

8520-8529

8530-8539

8540-8549

8550-8559

8560-8569

8570-8579

8580-8589

8590-8599

8600-8609

8610-8619

8620-8629

8630-8639

8640-8649

8650-8659

8660-8669

8670-8679

8680-8689

8690-8699

8700-8709

8710-8719

8720-8729

8730-8739

8740-8749

8750-8759

8760-8769

8770-8779

8780-8789

8790-8799

8800-8809

8810-8819

8820-8829

8830-8839

8840-8849

8850-8859

8860-8869

8870-8879

8880-8889

8890-8899

8900-8909

8910-8919

8920-8929

8930-8939

8940-8949

8950-8959

8960-8969

8970-8979

8980-8989

8990-8999

9000-9009

9010-9019

9020-9029

9030-9039

9040-9049

9050-9059

9060-9069

9070-9079

9080-9089

9090-9099

9100-9109

9110-9119

9120-9129

9130-9139

9140-9149

9150-9159

9160-9169

9170-9179

9180-9189

9190-9199

9200-9209

9210-9219

9220-9229

9230-9239

9240-9249

9250-9259

9260-9269

9270-9279

9280-9289

9290-9299

9300-9309

9310-9319

9320-9329

9330-9339

9340-9349

9350-9359

9360-9369

9370-9379

9380-9389

9390-9399

9400-9409

9410-9419

9420-9429

9430-9439

9440-9449

9450-9459

9460-9469

9470-9479

9480-9489

9490-9499

9500-9509

9510-9519

9520-9529

9530-9539

9540-9549

9550-9559

9560-9569

9570-9579

9580-9589

9590-9599

9600-9609

9610-9619

9620-9629

9630-9639

9640-9649

9650-9659

9660-9669

9670-9679

9680-9689

9690-9699

9700-9709

9710-9719

9720-9729

9730-9739

9740-9749

9750-9759

9760-9769

9770-9779

9780-9789

9790-9799

9800-9809

9810-9819

9820-9829

9830-9839

9840-9849

9850-9859

9860-9869

9870-9879

9880-9889

9890-9899

9900-9909

9910-9919

9920-9929

9930-9939

9940-9949

9950-9959

9960-9969

9970-9979

9980-9989

9990-9999

ZELIKMAN, A. N.

The cementation phase in hard alloys with a tungsten-carbide base,
Metallurgy of Non-Ferrous Metals, Moscow, 1946. Collection of
Scientific Works No. 14, Moscow Inst. of Non-Ferrous Metallurgy.
Report U-3391, 22 April 1953.

ZELIKMAN, A. N.

USSR/Metals
Titanium Compounds
Nitrogen

Jul/Aug 1947

"Nitrogen in Titanium Carbide and Titanium Tungsten Hard Alloys," A. N. Zelikman, Candidate in Technical Sciences, S. S. Isaeva, Tseytina, Kogre, Ministry of Nonferrous Metallurgy and Gold, and the Institute of Hard Alloys, 8 pp

"Navyette Metalloy" No 4

Titanium tungsten is the hard alloy used to coat the cutting edges of steel-working tools. The production of these hard alloys has therefore considerably increased. Tables of the percentage composition of

247/4

USSR/Metals (Contd.)

Jul/Aug 1947

various types of hard alloys and four photographic plates showing the microstructure of four samples of this alloy. Decarburization of titanium carbide is conducted in furnaces at temperatures of 1200 - 1800 degrees. Nitrogen appears to be the only effective decarburization agent at temperatures of 1800 - 2000 degrees. Nitrogen does not decrease the cutting efficiency of hard alloy tools.

247/4

COMMON ELEMENTS										COMMON VARIABLES INDEX									
PROCEDURES AND PROPERTIES INDEX										PROCEDURES AND PROPERTIES INDEX									
<p>Study of the Reaction Between Nitrogen and Titanium Carbide. (In Russian.) A. S. Zeldman and N. N. Gorovits. <i>Zhurnal Prikladnoi Khimii</i> (Journal of Applied Chemistry), v. 23, July 1950, p. 689-695.</p> <p>Nitration of TiC in the range 1300-1800°C. was investigated at subatmospheric pressures. It was found that degree of nitration decreases with increasing temperature at a given pressure. Method of investigation is described. Data are tabulated and charted. 11 ref.</p>																			
<p>ASH-SLA METALLURGICAL LITERATURE CLASSIFICATION</p>																			
<p>GROUPS</p>										<p>GROUPS</p>									

ZELIKMAN, A.N.; SAMSONOV, G.V.; KREYN, O.Ye.; STEPANOV, I.S., inzhener, retsenzent; TANANAYEV, I.V., retsenzent; POGODIN, S.A., professor, doktor, zaslushennyy deyatel' nauki i tekhniki, retsenzent; ROME, Ye.Ye., professor, doktor, retsenzent; ABRIKOSOV, N.Kh, doktor khimicheskikh nauk, retsenzent; SHAMRAY, F.I., doktor khimicheskikh nauk, retsenzent; MOROZOV, I.S., kandidat khimicheskikh nauk, retsenzent; BOOM, Ye.A., kandidat khimicheskikh nauk, retsenzent; NIKOLAYEV, N.S., kandidat khimicheskikh nauk, retsenzent; ZVORYKIN, A.Ya, kandidat khimicheskikh nauk, retsenzent; BASHILOVA, N.I., kandidat khimicheskikh nauk, retsenzent; VYSOTSKAYA, V.N., redaktor; KAMAYEVA, O.M., redaktor; ATTOPOVICH, M.K., tekhnicheskij redaktor

[Metallurgy of rare metals] Metallurgiya redkikh metallov. Moskva, Gos. nauchno-tekhn. izd-vo lit-ry po chernoi i tsvetnoi metallurgii, 1954. 414 p.
(MLRA 7:9)

1. Chlen-korrespondent Akademii nauk SSSR (for Tananayev)
(Metals, Rare--Metallurgy)

"APPROVED FOR RELEASE: 07/19/2001

CIA-RDP86-00513R001964410001-5

APPROVED FOR RELEASE: 07/19/2001

CIA-RDP86-00513R001964410001-5"

Metallurgy of Rare Metals

820

were written by G.A. Meyerson,; Chapters I-III, V, VI, VIII-XII, XVII-XXII, by A.N. Zelikman. The authors express their thanks for suggestions received from the reviewers and from scientific workers in the Department of Metallurgy of Light Metals of the Moskovskiy institut tsvetnykh metallov i zolota (Moscow Institute of Nonferrous Metals and Gold), at the Gosudarstvennyy nauchno-issledovatel'skiy institut po redkim metallam (State Scientific Research Institute for Rare Metals), and at the Vsesoyuznyy nauchno-issledovatel'skiy institut po tverdym splavam (All-Union Scientific Research Institute for Hard Alloys). There are 375 references, of which 205 are Soviet, 126 English, 40 German, 3 French, and 1 Italian.

TABLE OF CONTENTS:

Preface	9
Introduction	11
1. Definition of the term "rare metals"	11
2. Classification of rare metals	17
3. History of the development of the rare-metals industry in the USSR	21
4. Survey of basic technological methods of extracting rare metals from ores	24

Card 2/13

Card 1/1 Pub. 147 - 15/22

Authors : Zelikman, A. N., and Kreyn, O. Ye.

Title : Thermal dissociation of MoS_2

Periodical : Zhur. fiz. khim. 29/11, 2081-2085, Nov 1955

Abstract : The elasticity of MoS_2 (molybdenum disulfide) was investigated at temperatures ranging from 800 to 1,100° by means of a static method on the basis of the equilibrium composition of the gaseous phase during the reduction of MoS_2 with hydrogen. The results obtained were compared with those of N. Parravano (Italy) and K. K. Kelley (USA) and found to correspond perfectly with each other. Ten references: 4 USSR, 3 French, 2 Ital. and 1 USA (1900-1950). Tables; graph; drawing.

Institution : Moscow Inst. of Non-Ferrous Metals and Gold

Submitted : May 24, 1955

USSR/ Chemistry - Metallurgy

Card 1/1 Pub. 22 - 14/47

Authors : Zelikman, A. N.

Title : The reaction of the molybdenite mineral with MoO_3

Periodical : Dok. AN SSSR 100/6, 1083-1085, Feb 21, 1955

Abstract : The equilibrium and kinetics of the reaction between a pure molybdenite mineral (MoS_2) and MoO_3 were investigated. The reaction products were analyzed for their S content and then subjected to phase x-ray analysis. The effect of the gaseous MoO_3 on the rate of reaction is explained. It was found that the formation of MoO_2 during the calcination of molybdenite concentrates is possible only when the material clinkers during the calcination. Five references: 3 USA and 2 USSR (1937-1952). Tables; graphs.

Institution : The M. I. Kalinin Institute of Non-Ferrous Metals Including Gold, Moscow

Presented by: Academician G. G. Urazov, August 24, 1954

ZELIKMAN, A. N.

137-58-5-8788

Translation from: Referativnyy zhurnal, Metallurgiya, 1958, Nr 5, p 8 (USSR)

AUTHORS: Zelikman, A. N., Belyayevskaya, I. . . , Kreyn, O. Ye.

TITLE: A Study of FluoSolids Roasting of Molybdenite Concentrates
(Izucheniye protsessov obzhiga molibdenitovykh kontsentratov v
kipyashchem sloye)

PERIODICAL: Tr. Tekhn. soveshchaniya po obzhigu materialov v kipyash-
chem sloye. Moscow, Metallurgizdat, 1956, pp 75-96

ABSTRACT: A presentation of results of studies of oxidation rates of
molybdenite and of its interaction with MoO_3 , as well as of the
interaction of MoO_3 with CuO , CaO , FeO , and ZnO and of the
solubility in ammonia of molybdates formed in the process. The
process of FluoSolids roasting was studied in a laboratory fur-
nace with a cross section of 400x150 mm. The following was
established: optimal temperature: 5850-5950°C; specific output
of the hearth: 1.5-1.6 t/m²; extent of dust removal: 38-42 per-
cent; it was also established that the roasting process may be
carried out without fuel by means of utilizing the heat from the
reactions. Chemical composition and results of leaching of
cinder (which results from the FluoSolids roasting process)

Card 1/2

137-58-5-8788

A Study of FluoSolids Roasting of Molybdenite Concentrates

are shown, together with analogous information for an industrial roasting process carried out in a rotary furnace. Extraction of Mo from cinder, produced in the course of a process of FluoSolids roasting, is 92.0-93.5 percent as compared to the 79.0-79.5 percent achieved in the industrial process. The amounts of tailings from the two processes constitute 20-22 percent and 36-38 percent, respectively.

A. P.

1. Molybdenum ores--Processing
2. Molybdenum ores--Properties

Card 2/2

ZELIKMAN, A.N.

Category : USSR/Atomic and Molecular Physics - Statistical Physics
Thermodynamics

D-3

Abs Jour : Ref Zhur - Fizika, No 2, 1957 No 3480

Author : Zelikman, A.N., Gorovits, N.N., Prosenkova, T.Ye.

Title : Vapor Pressure of Molybdenum Trioxide at High Temperatures

Orig Pub : Zh. neorgan. khimii, 1956, 1, No 4, 632-637

Abstract : The vapor pressure of molybdenum trioxide was determined at temperatures above the melting point from the boiling temperatures at constant pressure. The following equation was derived for the vapor pressure of MoO_3 : $\log P = -7685/T + 8.26$. The latent heat of boiling of MoO_3 is 35.1 cal. Comparison of the vapor pressure determined by the jet method with the true vapor pressure confirm the assumption that the molybdenum trioxide molecules become polymerized in the gas phase. The probable composition of the gas molecules at temperatures of 950 -- 1000° corresponds to Mo_3O_9 .

Card : 1/1

ZELIKMAN, A. N.

Category: USSR / Physical Chemistry - Kinetics. Combustion.
Explosives. Topochemistry. Catalysis.

B-9

Abs Jour: Referat Zhur-Khimiya, No 9, 1957, 30040

Author : ~~Zelikman A. N.~~, Belyayevskaya L. V.

Inst : not given

Title : Study of the Reaction of Oxidation of Molybdenite

Orig Pub: Zh. neorgan. khimii, 1956, 1, No 10, 2245-2256

Abstract: It is shown that at 400, 500 and 600° molybdenite (I) is oxidized by oxygen of the air, directly to MoO_3 (II). Intermediate interlayer of MoO_3 , which is observed only at 600°, is formed as a result of secondary interaction between I and II. Rate and regularities of the oxidation of I, at different temperatures, depend on structure of oxidic envelope. At 600° this envelope is friable, velocity of the process is determined by velocity of the chemical reaction, extent of oxidation depends linearly upon duration, velocity constant $K = 0.0085 \text{ mm/minute}$. At 500°, as oxidation proceeds, there is observed a transition from kinetic conditions, over intermediate, to diffusion conditions, which are attained with a thickness

Card : 1/2

-15-

Category: USSR / Physical Chemistry - Kinetics. Combustion.
Explosives. Topochemistry. Catalysis.

B-9

Abs Jour: Referat Zhur-Khimiya, No 9, 1957, 30040

of the oxidic envelope of above 0.8 mm. The reaction is defined by the equation $x^n = kt$ (x is extent of oxidation, n varies from 1 to 2). At 400° a dense oxidic envelope is formed, the nature of the process is one of pure diffusion. A probable mechanism of oxidation of I is proposed, which is based on formation of intermediate compounds of the type of oxysulfides MoS_2O or $MoSO_2$.

Card : 2/2

-16-

ZELIKMAN, A.N.

Reactions in the solid phase with participation of molybdenum trioxide.
Zhur. neorg. khim. 1 no.12:2778-2791 D '56. (MIRA 10:6)
(Molybdenum oxides) (Chemical reactions)

Investigation of reciprocal reactions of molybdates of calcium, copper, and iron with solutions of sodium carbonate. A. N. Zelikman and L. V. Belvaevskaya. Zhur. Priklad. Khim., 1957, 10(50), 1717. C.A. 49, 7932j, 10753i. Molybdates of Ca, Cu, and Fe were prepd. by sintering at 600-650° for 8-12 hrs. stoichiometric mixts. of the respective oxides; CaMoO_4 was also prepd. as a check, by pptn. from aq. solns. Equil. of CaMoO_4 with Na_2CO_3 was reached slowly: 80-120, 24-48, and 10 hrs. at 25, 50, and 75°, resp. With 0.7% Na_2CO_3 some of the carbonate remained as NaHCO_3 , whereas with an initial concn. of 5% Na_2CO_3 such hydrolysis was not noted. The equil. consts., obtained graphically, were expressed by $\log K = -874.1/T + 3.124$ for pptd. CaMoO_4 , and $-839.1/T + 2.878$ for that prepd. from the oxides. The corresponding free energies were $\Delta F^\circ = -3099.9 + 15.29T$ and $-3839.7 + 13.18T$. With CuMoO_4 , two reactions took place: $(x+y)\text{CuMoO}_4 + (x+2y)\text{Na}_2\text{CO}_3 + 2\text{H}_2\text{O} = x\text{CuCO}_3 + y\text{Cu}(\text{OH})_2 + (x+y)\text{Na}_2\text{MoO}_4 + 2y\text{NaHCO}_3$, x and y varied, in part, as a function of the Na_2CO_3 concn., equil. was reached within 20-40 hrs., and at 60 and 75° all of the CuMoO_4 dissolved at the expense of 1.12 moles of Na_2CO_3 per mole of CuMoO_4 ; the solid phase approximated 1.5 $\text{CuCO}_3 \cdot \text{Cu}(\text{OH})_2$. At the expense of 0.5 mole of Na_2CO_3 per mole of molybdate the reaction was $\text{CuMoO}_4 + \text{Na}_2\text{CO}_3 = \text{CuCO}_3 + \text{Na}_2\text{MoO}_4$. The equil. consts. of the 1st reaction are $K_{60} = 33$ and $K_{75} = 53$. Equil. with FeMoO_4

ZELIKMAN, Abram Naumovich -- awarded sci degree of Doc Technical Sci for
the 20 May 57 defense of dissertation: "Oxidization firing of molyb-
den^{ite} ~~concentrates~~ concentrates (theory and practice of the process)" at
the Council, Mos Inst of Non-Ferrous Metals and Gold imeni Kalinin;
Prot No 2, 18 Jan 58.
(BMVO, 6-58, 12)

SOV/136-58-10-20/27
AUTHOR: Zelikman, A.N., Doctor of Technical Sciences, Professor
TITLE: Letters to the Editor (Pis'ma v redaktsiyu)
PERIODICAL: Tsvetnyye Metally, 1958, Nr 10, p 82 (USSR)
ABSTRACT: The author complains that he has been incorrectly named
as the editor of the book "Rare Metals of the Capitalist
Countries" by G.D. Kochergin. This book was reviewed
by I.S. Stepanov in Tsvetnyye Metally, 1958, Nr 8.

Card 1/1

SOV/136-52-11-9/21

AUTHORS: ~~Zelikman, I.N.~~ Bibikova, V.I.; Petrov, V.M.,
Postnikova, S.V., Abashin, G.I.; Pritulo, V.F. and
Nikitina, L.N.

TITLE: Study of the Behaviour and Recovery of Rhenium in the
Roasting of Molybdenite Concentrates in a Fluidized-Red
Roaster (Izucheniye povedeniya i ulavlivaniya reniya
pri obzhige molibdenitovykh kontsentrator v pechi
kipyashchego sloya)

PERIODICAL: Tsvetnyye Metally, 1958, Nr 11; pp 47-52 (USSR)

ABSTRACT: The rhenium concentration in some molybdenite
concentrates from ores of mainly copper-molybdenum
deposits reaches 0.02 - 0.10% and these are one of the
principle sources of the element. In 1956 a rare-
metals works adopted fluidised roasting; the composition
of a batch of concentrate being 49.35% Mo, 35.42% S
(total), 0.73% Cu, 2.98% Fe, 6.95% SiO₂, 0.38% Cu,
0.12% W, 0.025% Re, 0.033% Sa, trace of Te, 4.0% H₂O,
2.2% flotation reagents. The plant has a rotary kiln
and a fluidised roaster discharging into a common
electrostatic precipitator. Analysis of samples
(table 1) shows a 94.8-% distillation of rhenium in

Card 1/3

SOV/135-58-11-9/21

. Study of the Behaviour and Recovery of Rhenium in the Roasting of Molybdenite Concentrates in a Fluidized-Bed Roaster

the fluidized roaster, compared with 50% for the rotary kiln but the existing dust-catching system involved 79.5% loss of rhenium in the waste gases. A bubbler (fig.1) installation type VSPU designed by Gintsvetmet which could deal with part of the gas was tested and found to be 89-95% efficient with respect to rhenium, most (75-92%) of the quantity trapped being in the form of soluble compounds; the losses of liquid from the bubbler were shown to be due to evaporation rather than mechanical entrainment. Removal of pulp from the bubbler is recommended when pulp acidity becomes 30-60 g/litre and rhenium concentration 0.15 - 0.30 g/litre. The installation is recommended by the authors. The Mintsvetmetzoloto large laboratory fluidized roaster (fig.2) was used to study the behaviour of rhenium and its recovery in the roasting of low-grade molybdenite concentrates (20.5% Mo, 17.5% S (total), 18.31% SiO_2 , 4.06% Cu,

Card 2/3

SOV/136-52-11-9/21

. Study of the Behaviour and Recovery of Rhenium in the Roasting of Molybdenite Concentrates in a Fluidized-Red Roaster

1.60% CaO, 7.16% Fe, 0.21% W, 0.04% Re) at 590-630°C and an air velocity in the stack of 8-9 cm/sec (giving an hourly productivity of 75-80 kg/m² of hearth area). A materials balance (table 3) for a 12 hour run shows that the method is successful with such concentrates; the distillation of rhenium being 93.2% of the quantity in the concentrate. There are 2 figures and 3 tables.

Card 3/3

AUTHORS: Zelikman, A. N., Gorovits, N. N.

SOV/32-24-8-9/43

TITLE: The Precipitation of Tungsten in the Determination of this Element in Molybdenum Products (O soosazhdenii vol'frama pri opredelenii yego v molibdenovykh produktakh)

PERIODICAL: Zavodskaya Laboratoriya, 1958, Vol. 24, No 8, pp. 940 - 941 (USSR)

ABSTRACT: The methods for separating out tungsten from different molybdenum products are not yet sufficiently worked out. Usually a colorimetric method is used in which the pentavalent tungsten forms a yellow complex with a thiocyanogen salt. When the molybdenum concentration is preponderant a separation must first be carried out. This is accomplished by precipitating the tungsten with iron oxide, according to a report from the Institut tverdykh splavov MTsM SSSR (Institute for Hard Alloys MTsM USSR). The precipitated tungsten is then removed, dissolved in hydrochloric acid, and determined colorimetrically after the iron is first precipitated with lye. The completeness of the tungsten precipitation was investigated using the radioactive isotope tungsten-185 as an indicator.

Card 1/2

The Precipitation of Tungsten in the Determination of
this Element in Molybdenum Products

SOV/32-24-8-9/43

These investigations showed that 70-79% of the tungsten
is precipitated, so this method is not suitable for an
exact determination of tungsten in molybdenum products.
There are 1 table and 2 references which are Soviet.

ASSOCIATION: Moskovskiy institut tsvetnykh metallov i zolota im.M.I.Kalinina
(Moscow Institute for Nonferrous Metals and Gold imeni M.I.Kalinin)

Card 2/2

ZELIKMAN, A. N.

Spravochnik po mashinostroitel'nykh materialam v chetyrekh tomakh, tom 2; Tsvetnyye metally
i ikh splavy (Handbook on Machine-Building Materials in 4 vols., Vol. 2, Non Ferrous Metals
and Alloys) Moscow, Mashgiz, 1959, 639pp

Ch. IX. Rare Metals and Their Alloys

General information

Tungsten (Zelikman, A. N., Candidate of Technical Sciences)

Physical properties

Chemical properties

Metallurgy of tungsten

Methods of joining tungsten parts

Cleaning and etching

Mechanical properties

Fields of application

Tungsten alloys

Molybdenum (Zelikman, A. N.)

Physical properties

Card 15/22

446

446

447

447

450

451

452

452

452

453

453

456

456

Handbook on Machine-Building (Cont.)

80V/3505

Chemical properties	456
Metallurgy of molybdenum	459
Forming of molybdenum	459
Methods of joining molybdenum parts	460
Cleaning of the surface	460
Mechanical properties of molybdenum	460
Molybdenum alloys	464
Fields of application of molybdenum	467

Zirconium (Kislyakov, I. P., Candidate of Technical Sciences) 468

General characteristics	468
Chemical properties	470
Metallurgy of zirconium	476
Mechanical working of zirconium	476
Welding and soldering of zirconium and with zirconium	477
Mechanical properties of zirconium	478
Zirconium alloys	483

Vanadium (Kislyakov, I. P.)

491

Card 16/22

Handbook on Machine-Building (Cont.)

BOY/3505

Physical properties	491
Chemical properties	492
Metallurgy [extraction] and processing [powder metallurgy] of vanadium	493
Hot working and cold rolling	494
Applications of vanadium	499
Vanadium alloys	499
 Tantalum and niobium (Zelikman, A. N.)	 501
Physical properties	501
Chemical properties	504
Metallurgy of tantalum and niobium	509
Production of compact metal	509
Forming of tantalum and niobium	510
Cleaning and surface treatment	510
Alloys of tantalum and niobium	510
Applications of tantalum and niobium	514
 Beryllium (Kislyakov, I. P.)	 514
Card 17/22	

Handbook on Machine-Building (Cont.)

SOV/3505

General characteristics	514
Chemical properties	517
Metallurgy of beryllium	518
Melting and casting	518
Forming, machining, and welding of beryllium	518
Applications of beryllium	519
Beryllium-base alloys	519
Germanium (Zelikman, A. N.)	527
Physical properties	527
Chemical properties	530
Production of germanium	530
Machining of germanium	531
Applications of germanium	531
References	532
Ch. X. Hard Alloys (Tret'yakov, V. I., Candidate of Technical Sciences)	533
Sintered carbides for cutting tools	533
Card 18/22	

18.0000

75404
SOV/149-2-5-30/32

AUTHOR: Zelikman, A. N.

TITLE: Rare Metals of Chinese People's Republic

PERIODICAL: Izvestiya vysshikh uchebnykh zavedeniy. Tsvetnaya metallurgiya, 1959, Vol 2, Nr 5, pp 186-187 (USSR)

ABSTRACT: Until 1949 there was no production of rare metals in China; this also refers to tungsten, the reserves of which are very considerable; China's export of tungsten concentrates constituted about one half of world's output. The Soviet Union helped China develop its production by sending specialists and by permitting Chinese specialists to study in the Soviet Union. China now produces gallium, indium, thallium, selenium, and tellurium, which are prepared from byproducts of nonferrous metallurgy. Conventional methods of their preparation are described by the author but no names of plants or production figures are given. Ferrous alloys, ferromolybdenum, ferrotungsten, and carbides, and metallic tungsten and molybdenum are now produced in China, and there is no

Card 1/2

Rare Metals of Chinese People's Republic

75404

SOV/149-2-5-30/32

doubt that the Chinese People's Republic will become one of the most advanced producers of rare metals. There are 7 references, 3 Soviet, 1 Hungarian, 1 German, 2 U.S. The U.S. references are: Kleinert, The Mining Magazine, 85, 5, 146(1950) and Mills, Hunt, Turner, J. Electrochem. Soc., 100, 3, 126 (1953).

Card 2/2

PHASE I BOOK EXPLOITATION

SOV/4686

Zelikman, Abram Naumovich

Metallurgiya redkozemel'nykh metal'ov toriya i urana (Metallurgy of Rare-Earth Metals of Thorium and Uranium) Moscow, Metallurgizdat, 1960. 380 p. 3,650 copies printed.

Ed.: O.M. Kamayeva; Tech. Ed.: M.K. Attopovich.

PURPOSE: This textbook is intended for students of metallurgical and technological schools of higher education. It may also be useful to technical and scientific personnel.

COVERAGE: The author discusses processes for extracting the rare-earth elements thorium and uranium from various ores and concentrates, and describes methods for producing thorium and uranium metals and chemical compounds. Particular attention is given to methods of fractionating rare-earth elements. The principal physicochemical properties of these elements are discussed, and the area of their utilization is considered. Also included is information on pertinent minerals, ores, and concentrates. The

Card 1/7

Metallurgy of Rare-Earth Metals (Cont.)

SOV/4686

author thanks K.A. Bol'shakov, Professor G.Ye. Kaplan, Professor N.S. Greyver, and Professor N.N. Murach, Corresponding Members of the Academy of Sciences USSR, and their coworkers for their valuable comments, and A.I. Ginzburg, Doctor of Geological and Mineralogical Sciences, for reviewing paragraphs containing characteristics of various ores. There are 354 references: 194 Soviet, 138 English, 16 German, and 6 French.

TABLE OF CONTENTS:

Foreword

6

PART I. RARE-EARTH METALS AND THORIUM

- Ch. I. General Information on Rare-Earth Metals and Thorium
1. Electron structure of rare-earth elements and their place in the periodic arrangement of elements
 2. The place of thorium in the periodic arrangement of elements

7

Card ~~2/7~~

12

80834

S/149/60/000/03/04/009

5. 2100
15. 2220

AUTHORS: Kirillova, G.F., Meyerson, G.A., Zelikman, A.N. ²¹

TITLE: Kinetics of the Chlorination of Titanium and Niobium Carbides ²¹

PERIODICAL: Izvestiya vysshikh uchebnykh zavedeniy, Tsvetnaya metallurgiya, 1960, No 3, pp 90 - 96

TEXT: The method of preparing niobium and titanium chlorides from TiC and NbC, which may be obtained from oxides or directly from Ti and Nb concentrates, is of considerable interest. Information is given on results of investigations into kinetics of chlorinating pure Ti and Nb carbides. Carbide powders were used as initial material, obtained by the reduction of TiO₂ and Nb₂O₅ oxides with lamp black in a coal-tubular furnace in hydrogen atmosphere at 1,900° - 2,000°C and 1,700° - 1,800°C respectively. The chemical composition of the carbides is given in Table 1. The experiments were performed on compact cylindrical specimens contained in a tube; chlorine flow was passed through the tube at a certain speed and temperature; the loss in weight of the specimen was recorded as well as the amount of chloride developed during a given time interval. The experimental installation is shown

Card 1/3

80834

S/149/60/000/03/04/009

Kinetics of the Chlorination of Titanium and Niobium Carbides

in Figure 1. The weight loss of the specimens was the basic and most accurate indicator of the chlorination rate. The experimental results were expressed in the weight rate ($\text{g}/\text{cm}^2\cdot\text{min}$) or linear rate (mm/min) characterizing the extension of the process into the depth of the specimen. Computational data were checked by direct measurements with the aid of a binocular microscope ($\times 28$). Table 2 shows that the computational and measured values are in a satisfactory agreement. The following conclusions are drawn: The chlorination process was accompanied by the development of an external graphite layer whose effect on the rate of the process was not noticed at 400°C ; at 600° and 800°C a certain diffusional inhibition of the reaction was observed; chlorination acquired the characteristic of an intermediate process between the kinetic and diffusion processes, the first one being prevalent. It was established that the compact Nb carbide was chlorinated slower at 800° than at 600°C . This is apparently due to a higher adhesion strength of the graphite layer to the Nb carbide. The chlorination rate of Ti carbide increased rapidly at higher temperatures. The revealed dependence of the chlorination depth on the duration of the process was used to calculate the optimum time of chlorination of Ti and Nb carbide

Card 2/3

80834

S/149/60/000/03/04/009

Kinetics of the Chlorination of Titanium and Niobium Carbides

particles of different sizes at 400°, 600° and 800°C. This may play a part in the evaluation of the chlorination rates of powder-like carbides in a fluidized bed. There are 2 tables, 1 diagram, 3 sets of graphs and 6 references: 3 Soviet, 2 English and 1 German.

ASSOCIATION: Krasnoyarskiy institut tsvetnykh metallov (Krasnoyarsk Institute of Non-Ferrous Metals), Kafedra metallurgii redkikh metallov (The Chair of Metallurgy of Rare Metals)

SUBMITTED: December 10, 1959

Card 3/3

PETROV, V.M.; ZELIKMAN, A.N.

Study of roasting in a fluidized bed of unconditioned molybdenite concentrates. *Izv.vys.ucheb.zav.; tsvet.met.* 3 no.2:126-131 '60. (MIRA 15:4)

1. Krasnoyarskiy institut tsvetnykh metallov, kafedra metallurgii redkikh metallov.

(Ore dressing)

(Fluidization)

85457

17.4311

152200

2808, 1142, 1411, 1439

S/149/60/000/005/009/015
A006/A001

AUTHORS:

Meyerson, G.A., Zelikman, A.N., Belyavskaya, L.V., Tseytina, N.Ya.,
Kirillova, G.F.

TITLE:

Investigation Into Conditions of Titanium-Niobium Carbide Chlorina-
tion

PERIODICAL:

Izvestiya vysshikh uchebnykh zavedeniy, Tsvetnaya metallurgiya,
1960, No. 5, pp. 108-115

TEXT:

The authors investigated kinetics of complex titanium-niobium car-
bide chlorination and studied the process of chlorination in a fluidized bed on
a large-scale laboratory furnace. The former investigation was made with hot
pressed cylindrical specimens of titanium-niobium carbide, containing in %:
46.88 Ti; 13.91 Nb; 2.62 Si; 8.79 C_{bound}; 12.32 C_{free}; 3.76 N; 11.72 O etc.
Complex carbide was obtained from titanium-niobium concentrate and represented an
oxycarbonitride. Chlorination kinetics of complex carbide was investigated using
a horizontal quartz tube at 800, 600 and 400°C and 9 l/min chlorine feed. It was
found that chlorination of compact carbide specimens was accompanied by the forma-
tion of an external graphite layer. At 400°C the effect of this layer on the

Card 1/6

85457

S/149/60/000/005/009/015
A006/A001

Investigation Into Conditions of Titanium-Niobium Carbide Chlorination

chlorination rate was not noticeable (the process having a kinetic nature). At 600°C and, in particular, at 800°C, some diffusion inhibition of the reaction was observed due to the graphite layer formed. The nature of the chlorination process becomes intermediate between kinetic and diffusion one, the former being prevalent. The dependence of the chlorination depth on the duration of the process was revealed and used to calculate the maximum possible duration of chlorination of various-size carbide particles at 400, 600 and 800°C (Table 1) X

Card 2/6

85457

S/149/60/000/005/009/015
A006/A001

Investigation Into Conditions of Titanium-Niobium Carbide Chlorination

Table 1

Maximum possible duration of carbide particle chlorination

Temperature °C	Particle size mm	Duration of chlorination, min	
		in the presence of a graphite layer	without a graphite layer
800	0,250	8,0	5,58
800	0,075	2,8	1,68
800	0,042	1,2	0,94
600	0,250	17	13,6
600	0,075	5	4,1
600	0,042	3	2,3

Chlorination in a fluidized bed was studied on a furnace shown in Figure 4.

Card 3/6


85457

S/149/60/000/005/009/015
A006/A001

Investigation Into Conditions of Titanium-Niobium Carbide Chlorination

Figure 4

Furnace for the chlorination of complex carbide in a fluidized bed



- 1 - body; 2 - graphite lining; 3 - graphite grid; 4 - nichrome heater; 5 carbide bin; 6 - screw; 7 - reductor; 8-d-a-c motor; 9-fine graphite discharge pipes; 10-furnace discharge pipes; 11-powder graphite container; 12-thermo-couple; 13-frame; 14-tuyere; 15-heat insulation; 16-gas exhaust pipe.

Card 4/6

85459

S/149/60/000/005/011/015
A006/A001

Radiographic Investigation of Recrystallization Processes and Release of a Carbide Phase of Hard Alloys Containing Tungsten, Titanium and Tantalum Carbides




Figure 1

Phase diagram of the WC-TiC-TaC system; solubility of WC at 1,450 and 2,200°C are shown; the bi-phase range I contains a solid solution of TiC-TaC-WC and WC carbide; the mono-phase range II contains the TiC-TaC-WC phase; points 1 - 9 are the carbide components of the alloys investigated.

Card 5/6

85459

8/149/60/000/005/011/015
A006/A001

Radiographic Investigation of Recrystallization Processes and Release of a Carbide Phase of Hard Alloys Containing Tungsten, Titanium and Tantalum Carbides

There are 3 figures and 4 Soviet references.

ASSOCIATION: Moskovskiy institut stali (Moscow Steel Institute) Kafedra fiziki metallov i rentgenografii (Department of Physics of Metals and of Radiography)

SUBMITTED: October 27, 1959

Card 6/6

S/137/62/000/005/026/150
A006/A101

AUTHORS: Meyerson, G. A., Zelikman, A. N., Belyayevskaya, L. V., Tseytina, N. Ya., Kirillova, G. F.

TITLE: Processing of titanium-niobium rare-earth complex raw material by carbidization and chlorination

PERIODICAL: Referativnyy zhurnal, Metallurgiya, no. 5, 1962, 13, abstract 5080 ("Sb. nauchn. tr. In-t tsvetn. met. im. M. I. Kalinina", 1960, v. 33, 175-185)

TEXT: The processing of Ti-Nb raw material by the method of carbidization and chlorination was conducted on a laboratory and enlarged scale. The method consists in heating a mixture of the concentrate with coal in an electric furnace at 1,800 - 1,900°C. The complex raw material elements are then transformed into carbides and divided into the following two groups according to their properties: 1) TiC, NbC, TaC; SiC - strong refractory compounds, and 2) carbides of rare earth elements Ca, Na, Al and Fe, dissolving in diluted acids. Processing of a carbidization product with 10% HCl makes it possible to separate all soluble elements from refractory carbides. The washed and dried residue (solid solution

Card 1/2

Processing of titanium-niobium ...

S/137/62/000/005/026/150
A006/A101.

of Ti, Ni, Ta carbides) is chlorinated at 800°C with subsequent separation of chlorides in condensers and cleaning by rectification. Results of investigations are presented.

G. Svodtseva

[Abstracter's note: Complete translation]

Card 2/2

S/081/62/000/010/056/085
B168/B180

AUTHORS: Zelikman, A. N., Gorovits, N. N.

TITLE: Extraction of molybdenum from oxidized ores and lean concentrates from sor formations

PERIODICAL: Referativnyy zhurnal. Khimiya, no. 10, 1962, 397, abstract 10K61 (Sb. nauchn. tr. In-t tsvetn. met. im. M. I. Kalinina, v. 33, 1960, 186-201)

TEXT: A table is given showing the chemical make-up of oxidized ores and lean concentrates from sor formations. The following hydrometallurgical method of extracting Mo is examined: leaching with sulfuric acid and diluting with solutions of NaOH or soda (leaching conditions: soda concentration 2%; solid: liquid = 1 : 3; temperature 120°C, time 6 hr). A scheme is given for an autoclave-soda process for extracting Mo. Combined methods of extracting Mo, namely calcining with NaCl and soda and the 'chloride sublimation' method, were investigated. The technological characteristics of various schemes of Mo extraction are

Card 1/2

Extraction of...

S/081/62/000/010/056/085
B168/B180

compared. From the point of view of outlay on reagents and equipment the 'chloride sublimation' method, in which $\leq 2\%$ by weight of the material being processed goes into the hydrometallurgical operation (absorption of molybdenum oxychloride by ammonia solution), is the most economical. With the remaining schemes the entire mass of lean concentrates is used in leaching, which means that a large amount of apparatus must be installed for the leaching, concentration and filtration of pulps, with occupation of a correspondingly large amount of floor space.

[Abstracter's note: Complete translation.]

Card 2/2

5.2000,15.6600

77499

SOV/80-33-1-8/49

AUTHORS: Zelikman, A. N., Kreyn, O. Ye.

TITLE: Preparation of Molybdenum Disulfide for Lubrication Purposes

PERIODICAL: Zhurnal prikladnoy khimii, 1960, Vol 33, Nr 1, pp 49-55 (USSR)

ABSTRACT: The lubricating properties of natural MoS_2 (molybdenite), supplied by the Sobin Refining Plant, and of synthetic MoS_2 , were compared by testing both materials in oil suspension in TsNIIMASH and VIAM friction testing machines. The lubricating properties of both additives were practically equal. Synthetic MoS_2 was obtained: (1) on fusing MoO_3 with sulfur and sodium carbonate; optimum conditions: sulfur in 15% excess, temperature 700°C , time of reaction 1 hr; (2) on fusing CaMoO_4 with sulfur and sodium carbonate; optimum conditions:

Card 1/2

Preparation of Molybdenum Disulfide
for Lubrication Purposes

77499

SOV/80-33-1-8/49

sulfur in 60% excess, temperature 600-700° C, time
of reaction 1 hr. There are 5 figures; 5 tables; and
7 references, 2 U.S., 1 French, 3 German, 1 Soviet.
The U.S. references are: R. E. Bell, R. E. Herfert, J.
Am. Chem. Soc., 79, 13, 3351 (1957); R. L. Graham,
L. G. Hepfer, *ibid.*, 78, X, 19, 4846 (1956).

SUBMITTED:

January 19, 1959

Card 2/2

S/697/61/000/000/004/018
D228/D303

AUTHORS: Zelikman, A. N., Bibikova, V. I., Petrov, V. M., Postnikova, S. V., Abashin, G. I., Pritulo, V. F. and Nikitina, L. N.

TITLE: Study of the behavior and recovery of rhenium during the roasting of Kadzhara and Koundrad molybdenite concentrates in a boiling layer

SOURCE: Akademiya nauk SSSR. Institut metallurgii im. A. A. B. kova. Institut mineralogii, geokhimii i kristalloghimii redkikh elementov. Mezhdovedomstvennaya komissiya po redkim metallam. Vsesoyuznoye soveshchaniye po probleme reniya. Moscow, 1958. Reniy; trudy soveshchaniya. Moscow, Izd-vo AN SSSR, 1961, 42-50 ✓

TEXT: The authors present the results of their study of: (a) the distribution of Re in the products obtained from roasting Kadzhara molybdenite concentrates in a boiling-layer furnace, (b) the recovery of Re from waste gases of a boiling-layer furnace by means

Card 1/3

Study of the behavior ...

S/697/61/000/000/004/018
D228/D303

of a bubbling unit, and (c) the behavior of Re during the calcining of Koundrad concentrates in the same type of furnace and the extraction of Re with a similar bubbling unit. A tentative scheme is also suggested for reprocessing bubbler pulp to obtain metallic Re. It is noted that recent research at the Institut tsvetnykh metallov im. M. I. Kalinina (Institute of Non-Ferrous Metals im. M. I. Kalinin) has indicated the advantages of the boiling-layer furnace as compared with tubular, muffle, and reverberatory types. Diagrams illustrate the dust-collection system of the boiling-layer furnace, the bubbling unit designed by the Gintsvetmet (State Institute of Non-Ferrous Metallurgy) for the recovery of furnace gases, and the laboratory model of the boiling-layer furnace employed by the authors in their tests. The Re distribution in the roasting products of Kadzhara concentrates, the Re content of bubbler pulp, and the Re balance for both the bubbler and the furnace as a whole are given in tables. Conclusions: 1) The roasting of Kadzhara concentrates in a boiling-layer furnace ensures the fullest sublimation of Re; 92 - 96% of the Re is sublimated in this type of furnace

Card 2/3

Study of the behavior ...

S/697/61/000/000/004/018
D228/D303

as compared with only 50 - 67% in muffle and rotary tubular furna-
—ces. 2) The existing dust-collection system of the boiling-layer
furnace does not guarantee a satisfactory degree of Re extraction,
since the loss of metal in waste gases amounts to about 80%. The
lowering of the temperature of the Cottrell filter to 55 - 80° does
not reduce this loss on account of the condensation of H_2SO_4 . 3)
Much better results can be obtained with the bubbling unit, and the
bubbler's efficiency with respect to Re is stated to equal 89 - 96%.
75 - 92% of the metal in the bubbler pulp is in solution, and the
concentration of dissolved Re rises as the duration of the bubbling
lengthens. It is recommended that the pulp be removed from the bubb-
ler when the Re concn. and acidity of the solution is 0.15 - 0.3 and
30 - 50 g/l respectively. 4) The high degree of Re sublimation (92-
93.2%) from the ash of Koundrad concentrate shows that the same
technique can also be applied to this material; there is no diffe-
rence in the behavior of Re during the roasting of both concentra-
tes and the processing of their gaseous products in the bubbling
unit. There are 3 figures and 4 tables. / Abstracter's note: p.48
Card 3/3
of the photostat copy is illegible. /

BAL'SHIN, M.Yu., kand.tekhn.nauk; VINOGRADOV, S.V., inzh.; GLAZUNOV, S.G.,
 kand.tekhn.nauk; ZELIKMAN, A.N., kand.khim.nauk; KISLYAKOV, I.P.,
 kand.tekhn.nauk; KURITSINA, A.D., kand.tekhn.nauk; LEBEDEV, A.A.,
 A.A., inzh.; LUZHNIKOV, L.P., kand.tekhn.nauk; POMERANTSEV, S.N.,
 inzh.; RUDNITSKIY, A.A., doktor khim.nauk; SMIRYAGIN, A.P., kand.
 tekhn.nauk; TRET'YAKOV, V.I., kand.tekhn.nauk; CHURSIN, V.M.,
 kand.tekhn.nauk; CHUKHROV, M.V., kand.tekhn.nauk; SHAROV, M.V.,
 kand.tekhn.nauk, SHPAGIN, A.I., kand.tekhn.nauk; SHPICHINITSKIY,
 Ye.S., kand.tekhn.nauk; POGODIN-ALEKSEYEV, prof., doktor tekhn.
 nauk, red.; BOCHVAR, M.A., inzh., red.toma; RYBAKOVA, V.I., inzh.,
 red.izd-va; SOKOLOVA, T.F., tekhn.red.; MODEL', B.I., tekhn.red.

[Handbook of materials used in the machinery industry; in four
 volumes] Spravochnik po mashinostroitel'nyim materialam; v chety-
 rekhn tomakh. Pod red. G.I.Pogodina-Alekseeva. Moskva, Gos.nauchno-
 tekhn.izd-vo mashinostroit.lit-ry. Vol.2. [Nonferrous metals and
 alloys] TSvetnye metally i ikh splavy. Red.toma M.A.Bochvar.
 1959. 639 p.

(Nonferrous metals)

(Nonferrous alloys)

(MIRA 13:1)

(Machinery industry)

MEYERSON, G.A.; ZELIKMAN, A.N.; BELYAYEVSKAYA, L.V.; TSEYTINA, N.Ya.;
KIRILLOVA, G.F.

Processing of complex titanium-niobium bearing rare earth
minerals by the carbidizing and chlorination method. Sbor.
nauch. trud. GINTSVETMET no.33:175-185 '60. (MIRA 15:3)
(Titanium ores) (Rare earths)

ZELIKMAN, A.N.; GOROVITS, N.N.

Molybdenum recovery from "Sorskoje" deposit oxidized ores and
low-grade concentrates. Sbor. nauch. trud. GINTSVETMET no.33:
186-201 '60. (MIRA 15:3)

(Molybdenum ores) (Ore dressing)

ZELIKMAN, A.N.; LYAPINA, Z.M.

Separating tungsten and molybdenum from solutions of sodium tungstate and molybdate by hydrogen reduction under pressure. Izv.vys.ucheb.zav.; tsvet.met. 3 no.2:119-125 '60. (MIRA 15:4)

1. Krasnoyarskiy institut tsvetnykh metallov, kafedra metallurgii redkikh metallov.

(Tungsten---Metallurgy) (Molybdenum---Metallurgy)

18-3100

25548

S/149/61/000/004/005/008
A006/A101

AUTHORS: Zelikman, A. N.; Pritulo, V. F.

TITLE: Investigating the autoclave method of rhenium production from potassium perrhenate

PERIODICAL: Izvestiya vysshikh uchebnykh zavedeniy, Tsvetnaya metallurgiya, no. 4, 1961, 111-120

TEXT: Information is given on the autoclave method of rhenium precipitation from potassium perrhenate solutions at elevated temperatures and high hydrogen pressure. The authors studied the effect of the medium (initial acidity of the solution), partial hydrogen pressure, temperature, time and potassium perrhenate concentration, on the rate and degree of rhenium deposition and on the composition of the deposits and the metallic powder obtained. The investigation was made with the participation of graduate A. Peredereyev, on a stainless steel 1-liter autoclave with a magnetic mixer designed by Vishnevskiy. The section of the mixer that is located in the reaction zone and the impeller, are made of titanium. The autoclave was heated by a dismountable electric furnace whose temperature was regulated by an electronic potentiometer ЭПД-12 (EPD-12). The

Card 1/3

25548

S/49/61/000/004/005/008
A006/A101

Investigating the autoclave method ...

batch of potassium perrhenate was placed into a quartz glass container, filled with 200 ml distilled water and the rated amount of sulfuric acid. After heating the autoclave to a given temperature, the mixer was switched on and the hydrogen was added until the required partial pressure was attained. The pressure was maintained constant. The results of each experiment were evaluated from the rhenium content in the solution and in the washed and dried precipitate, and from changes in pH of the solution. Rhenium content in the solutions was determined by the photocalorimetric method and in the precipitates by the weight method. The precipitates were reduced with hydrogen to metal and the rhenium metal was analyzed as to its content of potassium sodium and calcium. It was found that 98 - 99% Re were precipitated into a deposit which contained rhenium particles and lower Re oxides under the following conditions: potassium perrhenate concentration 25 - 150 g/l; hydrogen pressure 10-60 atm.; temperature 200°C. It is shown that under optimum conditions of autoclave reduction ($KReO_4$ - concentration = 100 g/l; P_{H_2} = 60 atm.; t = 200°C; initial acidity 1.0 g-equ/l.; reduction time = 1 hour) rhenium powders do not contain over 0.002 - 0.003% admixtures of potassium, sodium and calcium. These values which are permissible in respect to the sintering properties of powder-pressed rhenium, correspond to the purity of rhenium obtained from ammonium perrhenate by the conventional

Card 2/3

Investigating the autoclave method ²⁵⁵⁴⁸ ...

S/149/61/000/004/005/008
A006/A101

method. Preliminary tests performed by engineer Ye. I. Pavlova, showed the possibility of using rhenium powders obtained by the autoclave method for sintering producing compact malleable metal. There are 7 figures, 6 tables and 10 references: 4 Soviet-bloc and 6 non-Soviet-bloc.

ASSOCIATIONS: Krasnoyarskiy institut tsvetnykh metallov (Krasnoyarsk Institute of Non-Ferrous Metals); Kafedra metallurgii redkikh metallov (Department of Metallurgy of Rare Metals)

SUBMITTED: April 12, 1961

X

Card 3/3

S/598/61/000/005/007/010
D040/D113

AUTHORS: Meyerson, G.A., Zelikman, A.N., Belyayevskaya, L.V., Tseytina, N.Ya., and Kirillova, G.F.

TITLE: Investigation of chlorination processes of titanium and niobium carbides, complex titanium-niobium carbide, and some other compounds


SOURCE: Akademiya nauk SSSR. Institut metallurgii. Titan i yego splavy, no. 5, Moscow, 1961. Metallurgiya i khimiya titana, 167-180

TEXT: The authors studied the reactions of titanium carbides and nitrides, niobium, complex Ti-Nb carbide, TiO and silicon carbide with chlorine in chlorination for obtaining $TiCl_4$. The experiments were conducted in view of the advantageous technological properties of titanium carbide and titanium carbonitride, the possible future use of the boiling layer for chlorinating them, and because precarbonization of rutile and ilmenite is used in foreign titanium production practice. Generalized results of the studies are given and a detailed illustrated description of the experimental equipment pre-

Card 1/3

Investigation of the chlorination processes ... S/598/61/000/005/007/010
D040/D113

sented. Titanium carbide, and titanium and niobium nitrides chlorinated fastest of all compounds, starting to chlorinate at 200°C. Active reaction of Nb carbide with chlorine was observed at 400°C, and of silicon carbide from above 600°C. Chlorination of TiO at a perceptible rate started from 300°C. In the range 400-700°C, the TiO chlorination degree was 50%, which is explained by the reaction



In the presence of carbon, TiO chlorinated much faster than a mixture of TiO₂ with carbon. Titanium carbide was prepared with lamp soot in a hydrogen atmosphere in a carbon-tube furnace at 2000°C, and niobium carbide in the same way at 1700-1800°C, and pressed into cakes with 110 kg/cm² and 325 kg/cm² pressure at 2150-2200°C and 2700-2750°C respectively. The chlorination of these carbides was accompanied by the formation of a graphite layer which did not affect the chlorination rate at 400°C but caused some inhibition at 600°C and 800°C. Ti-Nb carbide was produced by carbidization of loparite concentrate with subsequent washing in hydrochloric acid

Card 2/3

Investigation of the chlorination processes... S/598/61/000/005/007/010
DO40/D113

for separating the carbides of other elements, and its composition (in %) was 46.88 Ti, 13.91 Nb, 0.70 Ta, 2.62 Si, 8.84 C_{fixed}, 12.32 C_{free}, 3.76 N, 3.56 O, and 7.41 other elements. The constants of TiC chlorination rate were higher than of NbC, particularly at 800°C, and the chlorination rate of Ti-Nb carbide from loparite was close to the chlorination rate of pure TiC. The maximum necessary time for chlorination of carbide particles of different size at different temperatures has been determined. Chlorination of Ti-Nb carbide in the boiling layer was studied in a small laboratory furnace and in one of larger size, and proved feasible with the use of chlorine as well as chlorine with air. The TiCl₄ output rate from powder carbide in the boiling layer proved to be more than 10 times higher than in direct chlorination of oxides or concentrated ore in mixture with carbon. The chlorination degree of Ti-Nb carbide in the boiling layer amounted to 97-99%. There are 10 figures.

Card 3/3

ZELIKMAN, A.N.

Intercollegiate Conference on Methods of Separating Rare
Metals Having Similar Properties. Izv. vys. ucheb. zav.;
tsvet. met. 4 no.2:166-167 '61. (MIRA 14:6)
(Ore dressing—Congresses)
(Metals, Rare and minor)

ZELIKMAN, A.N.; PROSENKOVA, T.Ye.

Solubility of calcium, copper, zinc, iron and lead molybdates in
water and in dilute ammonia solutions. Zhur. neorg. khim. 6 no.1:
212-215 '61. (MIRA 14:2)

(Molybdates)

also 1583

22792
S/070/61/006/003/003/009
E021/E435

24,7100 (1160, 1136, 1142)

AUTHORS: Zelikman, A.N., Chistyakov, Yu.D., Indenbaum, G.V. and
Kreyn, O.Ye.

TITLE: Study of the crystal structure of molybdenum disulphide
prepared by different methods

PERIODICAL: Kristallografiya, 1961, Vol.6, No.3, pp.389-394

TEXT: The crystal structure of powdered MoS_2 prepared by five different methods has been investigated by X-ray analysis. Sample one was formed by the interaction of molybdenum trioxide with sulphur in fused soda; sample two by the interaction of calcium molybdenate with sulphur in fused soda; sample three by the interaction of molybdenum pentachloride with hydrogen sulphide; sample four by the interaction of molybdenum trioxide with sulphur vapour and sample five by the interaction of molybdenum with sulphur vapour. Further samples were also tested - sample six obtained by the thermal dissociation of molybdenum trisulphide and sample seven obtained by the interaction of molybdenum and sulphur and hot-pressed at 1200 to 1300°C. The X-ray photographs of these samples show that the structure of all the synthetic samples is a
Card 1/2

22792

X

S/070/61/006/003/003/009
E021/E435

Study of the crystal ...

new type different from both hexagonal α -MoS₂ and rhombohedral β -MoS₂. Fig.3 is a comparison of the results of X-ray studies for the three types of structure (a - α -MoS₂, 6 - β -MoS₂, B and 2 new structural type). Since the interplanar distance is the same in going from one form to another, it can be assumed that the layered lattice and the disposition of the sulphur atoms around the molybdenum is retained. It is proposed that the new form is hexagonal with c greater than in the lattice of β -MoS₂. Changes can be seen in the new structure depending on its method of preparation. This is explained by statistical interchanging of hexagonal and rhombohedral packing. The lubricating properties of the artificial MoS₂ are not different from those of natural MoS₂. There are 3 figures, 1 table and 11 references: 2 Soviet-bloc and 9 non-Soviet-bloc. The two references to English language publications read as follows: S.S.Berzelius. Pogg. Ann., 7, 261, 1826; R.E.Bell, R.Herfert, J.Amer.Chem.Soc., 19, 13, 3351, 1957.

ASSOCIATION: Krasnoyarskiy institut tsvetnykh metallov im.M.I.Kalinina
(Krasnoyarsk Institute of Non-Ferrous Metals imeni

SUBMITTED: September 5, 1960

M.I.Kalinina)

Card 2/4

22621

5,2300 1087,1228,1485

S/089/61/010/004/024/027
B102/B205

AUTHOR: Zelikman, A. N.

TITLE: Intercollegiate Conference on Methods of Separating Rare Metals Having Similar Properties

PERIODICAL: Atomnaya energiya, v. 10, no. 4, 1961, 405-406

TEXT: In the past few years, several Soviet institutes have studied and elaborated numerous methods for the separation of elements having similar properties. The mezhvuzovskaya konferentsiya po metodam razdeleniya blizkikh po svoystvam redkikh metallov (Intercollegiate Conference on Methods of Separating Rare Metals Having Similar Properties) took place at the Institut tsvetnykh metallov im. M. I. Kalinina (Institute of Non-ferrous Metals im. M. I. Kalinin) in November, 1960. It was attended by 250 delegates from 10 schools of higher education, 13 institutes of the Academies of Sciences of the USSR and of the Republics of the Union, and 20 scientific research institutes and plants. 56 reports were made within four days. Most of them (19) dealt with extraction by organic solvents, 13 with ion-exchange chromatography, and 9 with fractional crystallization and preci-

Card 1/3

Intercollegiate Conference on...

22621
S/089/61/010/004/024/027
B102/B205

pitiation. Some of these reports are discussed in the following. Ion-exchange methods: Among others, M. M. Senyavin spoke about "chromatographic synthesis of pure rare-metal preparations" and B. N. Laskorin about "ion-exchange and chemosorption processes in non-ferrous hydro-metallurgy". L. I. Martynenko and others spoke about ion-exchange separation of macroscopic quantities of rare earths; N. P. Kalonina, N. P. Magd, Ye. A. Subbotina, D. M. Chizhikov, and others about sorption methods of separating tantalum, niobium, and titanium; E. N. Laskorin, G. Ye. Kaplan, and A. M. Arzhatkin about chromatographic separation of zirconium and hafnium; D. I. Ryabchikov and others about the separation of selenium and tellurium by ion exchangers. Extraction methods. G. V. Korpusov held a synoptic report; V. A. Mikhaylov and V. G. Torgov spoke about the use of complexing agents in separating rare earths; Z. A. Sheka and Ye. Ye. Kriss about the use of organic extracting agents; N. I. Gel'perin, V. L. Pebalk, and others about the separation of the elements of the cerium group; A. I. Vaysenberg, T. F. Zhitkova, L. A. Kolchina, G. Ye. Kaplan, B. N. Laskorin, V. K. Kulifeyev, and V.Z. Nepomnyashchiy about the separation of tantalum, niobium, and titanium by cyclohexanone, tributyl phosphate, trioctyl amine, and other compounds; G. Ye. Kaplan and

Card 2/3

22021

Intercollegiate Conference on...

S/089/61/010/004/024/027
B102/B205

G. A. Yagodin about the separation of zirconium and hafnium; L. D. Motov and T. G. Loshtayeva about the extraction of zirconium and hafnium by cyclohexanone; M. V. Vinarov and others about the synthesis of hafnium by rhodanide extraction. Fractional precipitation and crystallization. Reports were made on the separation of titanium, niobium, and tantalum on the basis of their varying solubility in chlorine complex salts and sulfuric acid complex salts (D. M. Chizhikov, B. Ya. Tratskevitskaya, A. P. Shtin, A. K. Sharova, Ya. G. Goroshchenko, and others), and also on the separation of Rb and K (B. D. Stenin and V. Ye. Plyushchev). Distillation and rectification methods. L. A. Niselson held a synoptic report on separation and purification of zirconium, hafnium, niobium, and tantalum; A. N. Zelikman, O. Ye. Kreyn, V. N. Chernyayev, and V. V. Kranukhin spoke about the separation of tungsten and molybdenum. Other separation methods. Reports were made on the separation of zirconium and hafnium by selective reduction of their chlorides (V. A. Kozhelyakin, V. S. Yemel'yanov, A. I. Yevstyukhin, and others); electrolytic separation of zirconium and hafnium (V. M. Smirnov and others); electrolytic separation of rare earths (L. Ye. Ivanovskiy and others); and separation of tungsten and molybdenum by zone melting (P. I. Fedorov and N. V. Mokhosev). The proceedings of the Conference will be published this year by the publishing house Metallurgizdat.

Card 3/3

IORDANOV, Khr. V.; ZELIKMAN, A. N.

Kinetics of molybdenum oxidation in the solution of sodium hypochlorite.
Khim i industriia 23 no.6:171-175 '61.

2107
S/080/61/034/003
A057/A129

15.2130
5.2200

AUTHORS:

Zelikman, A. N., Kreyn, O. Ye., Gorovits, N. N.

TITLE:

Purification of molybdenum trioxide from tungsten and admixtures of some other elements

PERIODICAL:

Zhurnal prikladnoy khimii, v. 34, no. 3, 1961, 679 - 682

TEXT:

A preparative purification method for molybdenum trioxide from tungsten and other impurities is described. The method is based on distillation of molybdenum oxychloride by heating a mixture of molybdenum trioxide and sodium chloride. Thus the tungsten content can be decreased from an initial content of 0.01 to 1% W down to 10^{-4} - 10^{-3} % W. The present method was already published by A. N. Zelikman [Soviet patent no. 1131145 (1957)] and developed as a result of prior investigations [Ref. 1: ZhOKh, 24, 1916 (1954)]. Previous experiments demonstrated the reaction of MoO_3 with NaCl at 500° - 700°C resulting in formation of sodium molybdate and dioxychloride. The latter evaporates at this temperature. On the other hand it was observed that at 500° - 650°C tungsten trioxide does not react with sodium chloride forming volatile compounds. Tests for the present method were carried out with $\text{MoO}_3 + \text{WO}_3$ mixtures varying the ratio of $\text{W}/(\text{Mo} + \text{W})$ from 1 to 29%.

Card 1/3

27074
S/080/61/034/003/016/017
A057/A129

Purification of molybdenum trioxide from...

The mixtures were obtained by mixing an ammonium molybdate solution with ammonium tungstate solution with subsequent evaporation of the liquid and calcination (550° - 600°C) of the residue. The latter was then thoroughly mixed with finely ground sodium chloride, placed in a horizontal tubular oven and heated by passing air (about 10 l/hr). Molybdenum oxychloride sublimated, was dissolved and molybdenum and tungsten were determined. The latter was first determined colorimetrically by the method of the Vsesoyuznyy institut tverdykh splavov (All-Union Institute of Solid Alloys), but since this method was insufficient in further experiments a spectral method, developed in the MSU (Moscow State University) by N. I. Tarasevich et al. [Ref. 4: ZL, 8 (1959)] was applied. The obtained results (Table 1) demonstrate that the sublimates contain a maximum of about 0.001% W/(Mo + W), and independently of the composition of the mixture about 20% of molybdenum sublimates. Further tests were made with a quartz tubular oven (length 1 m, diameter 45 mm), using 200 g samples, passing air at a 20 l/hr rate, and heating to 650° - 700°C for 30 minutes. Thus a 20 - 22% extraction of molybdenum was effected. For tungsten contents of 0.004, 0.01, 0.03 and 1.035% in the initial material (MoO_3 from ammonium paramolybdate, molybdenic acid, or contaminated with WO_3) final products containing $8 \cdot 10^{-4}$, $8 \cdot 10^{-4}$, $6 \cdot 10^{-4}$, and $1.5 \cdot 10^{-3}$ % respectively of tungsten were obtained.

Card 2/4

Purification of molybdenum trioxide from...

27074
S/080/61/034/003/016/017
A057/A129

The purification degree in relation to other impurities is shown in Table 3: There are 3 tables, 1 figure and 4 Soviet-bloc references.

SUBMITTED: May 27, 1960

Table 1. Purification degree of molybdenum trioxide from tungsten impurities in experiments with 2 - 3 g batches. Temperature 600°C, duration of the experiments 1 hr.

Legend: (1) composition of the mixture, (2) ratio W/(Mo + W) (% in the initial mixture), (3) time of chlorination (min), (4) ratio W/(Mo + W) in the oxychloride (%), (5) extraction of molybdenum in the oxychloride (%), (6) traces.

Card 3/4

Состав смеси (1)	Отношение W (2) Mo + W (% в исходн. смеси)	Время хлорирования (мин.) (3)	Отношение W (4) Mo + W в оксихлориде (%)	Извлечение молибдена в оксихлориде (%) (5)
MoO ₃ + 1% WO ₃ + NaCl	1.19	30	1.70 · 10 ⁻³	21.54
	1.19	45	0.86 · 10 ⁻³	21.98
	1.19	60	1.00 · 10 ⁻³	19.92
MoO ₃ + 5% WO ₃ + NaCl	5.90	30	0.93 · 10 ⁻³	21.38
	5.90	45	0.91 · 10 ⁻³	21.83
	5.90	60	0.91 · 10 ⁻³	21.73
MoO ₃ + 25% WO ₃ + NaCl	28.80	30	Следы	20.04
	28.80	45	1.01 · 10 ⁻³	19.75
	28.80	60	1.01 · 10 ⁻³	18.91

ZELIKMAN, A.N., prof, doktor tekhn. nauk, red.; KOMISSAROVA, L.N., dots., kand. khim.nauk, red.; KRAPUKHIN, V.V., dots., kand. tekhn. nauk, red.; SEVRYUKOV, N.N., prof., doktor tekhn. nauk, red.; KAMAYEVA, O.M., red. izd-va; MIKHAYLOVA, V., tekhn. red.

[Separation of rare metals having similar properties] Razdelenie blizkikh po svoistvam redkikh metallov. Moskva, Metallurgizdat, 1962. 264 p.

(MIRA 15:8)

(Nonferrous metals--Metallurgy)

S/149/62/000/001/006/009
A006/A101

AUTHORS: Zelikman, A. N., Lyapina, Z. M.

TITLE: Separation of cerium from other rare-earth elements using the method of oxidation with oxygen under pressure

PERIODICAL: Izvestiya vysshikh uchebnykh zavedeniy, Tsvetnaya metallurgiya, no. 1, 1962, 115 - 120

TEXT: The authors studied the possibility of accelerating oxidation of Ce^{3+} in aqueous pulp of rare earth element hydroxides by pressure as developed in Oranienbaum (Germany). The acceleration can be achieved by the use of oxygen, and by raising the temperature and pressure. Experimental investigations were made on a 1-liter-autoclave with a Vishnevskiy electromagnetic mixer at 2,600 rpm. The solid-liquid ratio in the pulp was 1 : 5. The necessary alkalinity of the pulp was obtained by the addition of a 40% NaOH solution. To produce a neutral or weakly acid medium the pulp was neutralized with nitric acid. The pH value was determined with a JII-5 (LP-5) potentiometer with a glass electrode. The effect of the oxidation medium, the temperature and the method of preparing the hydroxide, on cerium oxidation in the pulp was investigated. Studying

Card 1/2

Separation of cerium from...

S/149/62/000/001/006/009
A006/A101

the effect of alkalinity, partial oxygen pressure and temperature on the rate and completeness of cerium oxidation, the following optimum conditions were found: pH = 10, oxygen pressure 5 - 10 atm; temperature 130°C. Under these conditions full Ce oxidation is obtained within 30 minutes. The rate of Ce³⁺ oxidation depends on the method of preparing the hydroxides; oxidation in a mixture of hydroxides precipitated from chloride solutions with ammonia, proceeds incompletely. In a mixture of hydroxides, obtained by the decomposition of bisulfates, or precipitated with caustic soda, cerium oxidation proceeds rapidly. Cerium concentrates with up to 95% CeO₂ content can be obtained. This article was recommended by the Kafedra metallurgii redkikh metallov (Department of Metallurgy of Rare Metals) at the Krasnoyarskiy institut tsvetnykh metallov (Krasnoyarsk Institute of Non-Ferrous Metals). There are 6 figures and 11 references, 9 Soviet-bloc and 2 non-Soviet-bloc.

ASSOCIATIONS: Krasnoyarsk Institute of Non-Ferrous Metals. Gosudarstvennyy nauchno-issledovatel'skiy i proyektnyy institut redkometallicheskoj promyshlennosti (State Scientific Research and Planning Institute of Rare-Metal Industry)

SUBMITTED: December 29, 1960

Card 2/2

S/020/62/035/007/004/013
D267/D307

AUTHORS: Zelilman, A.N., Kreyn. O.Ye., Nisel'son, L.A. and
Ivanova, Z.I.

TITLE: Separation of tungsten from molybdenum by the recti-
fication of their chlorides

PERIODICAL: Zhurnal prikladnoy khimii, v. 35, no. 7, 1962,
1467-1472

TEXT: WCl_6 and $MoCl_5$ were obtained from pure metals by
chlorination at 600-750°C, distilled in an argon atmosphere to separ-
ate the oxychlorides, after which WCl_6 with about 5% $MoCl_5$ or vice
versa were rectified on a plate column. It was found that the
impurity content of the purified chloride is less than 0.015%, and
that the yield of the rectified chloride is 70-80% of theoretical.
There are 5 figures and 3 tables. ✓

SUBMITTED: June 22, 1961

Card 1/1

ZELIKMAN, A. N.

(29)

The Second All-Union Conference on Rhenium, sponsored by the Institute of Metallurgy imeni A. A. Baykov, Academy of Sciences USSR, and the State Institute of Rare Metals, was held in Moscow 18-21 November 1962. A total of 335 representatives from 83 scientific institutions and industrial establishments participated. Among the reports presented were the following: autoclave extraction of Re from Cu concentrates (A. P. Zelikman and A. A. Peredereyev); Re extraction from the gaseous phase (V. P. Savrayev and N. L. Peysakhov); recovery of Re by sorption and ion interchange (V. I. Bibikova, V. V. Il'ichenko, K. B. Lebedev, G. Sh. Tyurekhodzhaeva, V. V. Vermilov, Ye. S. Raimbekov, and M. I. Filimonov); production of carbonyl Re (A. A. Ginzburg); electrolytic production of high-purity Re and electroplating with Re (Z. M. Sominskaya and A. A. Nikitina); Re coatings on refractory metals produced by thermal dissociation of Re chlorides (A. N. Zelikman and N. V. Baryshnikov); plastic deformation and thermomechanical treatment of Re (V. I. Karavaytsev and Yu. A. Sokolov); growth of Re single crystals and effect of O₂ on their properties (Ye. M. Savitskiy and G. Ye. Chuprikov); Re-Mo, Re-W, and Re-precious-metal alloys (Ye. M. Savitskiy, M. A. Tytkina, and K. B. Povarova); synthesis of Re nitrides, silicides, phosphides, and selenides (G. V. Samsonov, V. A. Obolonchik, and V. S. Neshpor); weldability of Re-Mo and Re-W alloys (V. V. D'yachenko, B. P. Morozov, and G. N. Klobanov); new fields of application for Re and Re alloys (M. A. Tytkina and Ye. M. Savitskiy); and Re-Mo alloy for thermocouples (S. K. Danishevskiy, Yu. A. Kocherzhinskiy, and G. B. Lapp). [WW]

Tsvetnyye metally, no. 4, Apr 1963, pp 92-93

S/078/62/007/011/004/005
B101/B186

AUTHORS: Baryshnikov, N. V., Zelikman, A. N., Teslit'skaya, M. V.
TITLE: Vapor pressure and composition of rhenium monoxytetrachloride vapor

PERIODICAL: Zhurnal neorganicheskoy khimii, v. 7, no. 11, 1962, 2634-2635

TEXT: Failing any data for the vapor pressure and composition of ReOCl_4 vapor, attempts were made to measure its vapor pressure with a Swietoslawski ebulliometer and the resulting values were compared with those from the jet method. It was found that oxydizing ReCl_5 with oxygen at relatively low temperatures ($150-180^\circ\text{C}$) produces only ReOCl_4 , which can easily be purified by rectification. The pressure of the ReOCl_4 vapor above the liquid ReOCl_4 phase follows the equation $\log p = -2380/T + 7.63 \text{ mm Hg}$; the latent heat of evaporation of liquid ReOCl_4 is $10.9 \pm 0.2 \text{ kcal/mole}$, and the boiling point calculated by extrapolation to 760 mm Hg is

Card 1/2

VOL'DMAN, G.M.; ZELIKMAN, A.N.

Equation for calculating the efficiency of a continuous action
fluidized bed. Izv. vys. ucheb. zav.; tsvet. met. 5 no.4:73-79
'62. (MIRA 16:5)

1. Moskovskiy institut stali; kafedra metallurgii redkikh metallov.
(Fluidization)

BARYSHNIKOV, N.V.; ZELIKMAN, A.N.

Thermodynamic properties of rhenium chlorides and oxychlorides.

Izv. vys. ucheb. zav.; tsvet, met. 5 no.6:98-110 '62.

(MIRA 16:6)

1. Moskovskiy institut stali i splavov, kafedra metallurgii
redkikh metallov.

(Rhenium chloride—Thermodynamic properties)

S/828/62/000/000/013/017
EO71/E135

AUTHORS: Zelikman, A.N., and Lyapina, Z.M.

TITLE: The separation of cerium from other rare earth elements using the method of oxidation with oxygen under pressure

SOURCE: Razdeleniye blizkikh po svoystvam redkikh metallov. Mezhvuz. konfer. po metodam razdel. blizkikh po svoyst. red. metallov. Moscow, Metallurgizdat, 1962, 148-154.

TEXT: The authors investigated the possibility of accelerating the process by the use of oxygen at increased temperatures (25-200 °C) and partial pressures (3-15 atm), using in the experiments a mixture of alkali earth hydroxides obtained from a melt of chlorides containing, %: 29.55 rare earth elements (of which 50% was CeO_2); 7.61 CaO; 2.37 SrO; 0.51 MnO; 0.23 Fe_2O_3 ; 0.43 ThO_2 . After solution of the chlorides in a 2% hydrochloric acid and purification from thorium and partially from iron and manganese, the rare earth elements were precipitated as acid sulphates and the latter decomposed with sodium hydroxide (in some cases directly precipitated with sodium hydroxide or with

Card 1/2

The separation of cerium from other ... S/828/62/000/000/013/017
E071/E135

ammonia). Oxidation was carried out in an autoclave fitted with an electromagnetic stirrer. The solid to liquid ratio in the pulp was 1:5. Results: it is possible to accelerate the oxidation of hydroxides of rare earth elements in an aqueous pulp with oxygen under pressure. Optimum conditions: pH = 10, oxygen pressure 10 atm, temperature 130 °C. Under these conditions complete oxidation of cerium is achieved in 30 minutes. The velocity of oxidation of Ce^{3+} depends on the method of preparation of the hydroxides. Oxidation in the mixture of hydroxides, precipitated from a solution of chlorides with ammonia, is incomplete; Ce oxidises rapidly in a mixture of hydroxides produced by decomposition of acid sulphates, or precipitated with sodium hydroxide. After the oxidation, cerium was separated from other rare earth elements by treatment with a 10% nitric acid. Concentrates containing up to 95% of CeO_2 can be obtained.

There are 6 figures.

Card 2/2

S/828/62/000/000/016/017
E071/E135

AUTHORS: Zelikman, A.N., Kreyn, O.Ye., Nisel'son, L.A.,
Gorovits, N.N., and Ivanova, Z.I.

TITLE: Separation of tungsten and molybdenum by utilising the
difference in volatility of their chlorides and
oxychlorides

SOURCE: Razdeleniye blizkikh po svoystvan redkikh metallov.
Mezhvuz. konfer. po metodam razdel. blizkikh po svoyst.
red. metallov. Moscow, Metallurgizdat, 1962, 186-197.

TEXT: A method of separating tungsten from molybdenum, based
on evaporation of MoO_2Cl_2 on heating of molybdenum trichloride
with sodium chloride to a temperature of 600-700 °C, was studied.
With contents of 0.01 to 0.16 and 1.035% W in the starting
molybdenum trioxide the purified product contained less than
(6 to 9) $\times 10^{-4}$ and 1.5×10^{-3} % W respectively. It was established
that it is possible to separate tungsten and molybdenum by
rectification of their higher chlorides, WCl_6 and MoCl_5
(rectification column data: diameter 30 mm, height 600 mm,
15 sieve plates, with 45 holes of 1 mm diameter).

Card 1/2